


"POLYSHADE"

Polyshade demonstrates a new pedagogical model that applies parametric design to the traditional design-build studio. This approach aims to establish a fully associative collaboration across a professional team established for the construction of a small building. In working with local architects Polyshade aims to create a "proto practice" studio environment that furthers the mutual concerns of education and practice.

The specific goals of the Spring 2010 session centered on creating an actively cooled, shaded environment for a community garden within university campus housing. The project extends the sustainable practice of an existing grad/faculty housing organization by proposing an outdoor learning/gathering space that mitigates heat stress in extreme temperatures. The students worked within the constraints of a stakeholder client base, a specific site, budget and an agreed collaboration with local architects (chosen for their experience and vested interest in the site).




This collaborative experience extended to the architect's consultants as the project developed. Consultations were carried out at strategic points during the project with structural engineers (Tony Polusny MBJ), pre-project costing (Andy Hill DPR), PV/Solar (Nate Zachreson ESD) among others.

Collaboration/Cooperation

Description	Manager &	-		% Reduct.	Sundotar
Mac. Ble Denotion	800	#	1.5		\$1,200.00
					\$1,700.0
fo Work	111				2-227
Cultur Fit at Seating Area Bach-fit and Fine Grading			176		Salvana:
Existing Utilly Retocation					
Delots Bux		**	360		pea
Site Temporary Fence	392	•	4		\$1/expos
Profect existing to retain plants	1	LB	500		pena
Patch back entiting landscape Recycled concerns parents	200	ŕ	:		\$1,000.00
n.i.	40	7.	73		-
					\$1,000.0
Subchasture - Etia Congreta Footrigs (Or a fire 101)	14	q	275	79%	\$1,527,50
HS double each way repar	188	-			55555000
management		LB	1300		h'ma
					\$6,107.6
uperstructure Non structure transco	3	-	4500	75%	\$10,125.00
Cross members	10	**	1000	79%	\$7,60000
Hat structure top reign		00	563	1976	\$1.HT
Het structure bottom dras	4	60	963	79%	\$1,600 cm
Half structure verticals		CO	563	72%	\$1,500 m
Hat structure standoffs Georging (soup, fir) assume: 2" gap between each 194	300	50	50	79%	No.
Dry fit	1	ь	990		1000
Shop labor	240	hrs	62		\$14,0000
Engineering	-60	hra	96.8		FL02:
Transport Erection	1	LS	16,685		P6.96.0
Pelot Medi	1	re.	2500	72%	\$1,575.00
					802,514.0
sedifical Solar Panets			0		
Inquistral Fan	100	50	100		\$1,000 mm
Inverter (Morningster Suresine 300W 12v		60	268		223.00
15h x 12h x 5h chooserc and backeletc		60	55.54		\$4 E. S
Heavy duty sost switch (12/lec, 20A) Y Bussman JULN fuse and fuse holder writermination lugs (12/lec, 100A)	:	60	16.34		B1 B72
T Bussman JUN fuse and fuse holder w/fermination lugs (120Vac. 3A)	i	60	12.76		81820
S/Bin x Bft copper grounding electrode		00	11.12		200
6 AWG	80	*	0.51		193.0
8 AWS 500 sood	1	*	0.36 68		W/U
15 /ANO 500% scool	100	EA.	35.21		EB3
					\$2,415.0
oballs Management Project engineer		**	2400		\$9,600,00
Project accountant	10	-	55		Sec. or
					\$16,160.0
contra Officer Computer	1.	mo	475		\$475.00
Cer Prone	1	mo	110		211000
Vehicles/Travel					\$585.0
Truck rental, small	1	mo	900		\$900.00
fuel-trucks, cars	1	mo	300		\$300.00
Farmanana, Caminas					\$1,200.0
Temporary Services Temp. toilets	1	mo	125		\$125.00
Construction signage	1	mo	200		\$200.00
					\$325.0
Prod. of the					****
Project Subtotal					\$92,511.1° \$925.1°
	170				\$925.1 \$1,156.3
Subguard Insurance					
	1.25%				\$9,251.1
Subguard Insurance Payment and Performance Bond Construction Contingency Contractor's Insurance	1.25% 10.00% 1.75%				\$9,251.1 \$1,618.9
Subguard Insurance Payment and Performance Bond Construction Contingency Contractor's Insurance GC Fee	1.25% 10.00% 1.75% 4.33%				\$9,251.1 \$1,618.9 \$4,005.7
Subguard Insurance Payment and Performance Bond Construction Contingency Contractor's Insurance	1.25% 10.00% 1.75% 4.33% 5.24%				

Students were regularly involved in construction budget estimation for full-fabrication. In this instance the students were involved in four stages of estimation carried out with the architects recommended consultants (Andy Hill. DPR preconstruction management). Students establish a parametric model based on quantitive information required by the consultants i.e. excavation, length and diameter of pipe sections, linear length for Trex cladding, areas for paintwork and required electrical and solar equipment.



Legend

4

- 1. Primary Structure span and height (linked to diameter pipe section).
- 2. Distribution of shading slats according to solar orientation.
- 3. Orientation of solar panels fixed to south at an angle of 22 degrees.
- 4. "Hat" adjustments according to fan cooled zones.
- 5. Secondary structural section




Computers/Technology


Polyshade provides an understanding and development of advanced roles of "Computer/Technology" in providing information for costing and construction. Particularly an understanding of practice of parametric design. (Boyer Table 8). From the outset the students were encouraged to is to build a fully parametric model that connects associatively to cost, structural and environmental considerations. Our aim is to provide an efficient understanding of the consequences of adjustments to the design through the practice of masscustomization and delayed differentiation. In this case we developed a Rhino/Grasshopper parametric definition that would provide quick updates to design modifications. The choice of these programs instead of Revitt/Archicad lay in the grassroots learning of associative links and how to visualize and create them. This provides an "inside the box" experience we felt was crucial to the student's ability to judge why and when they should use industry-standard BIM programs when they became practitioners. It also served to introduce the Rhino/Grasshopper parametric model to the architects.


Legend - Parametric Diagram

- 1. Intersection points for primary structure modified individually (u and v direction).
- 2. Ceiling cell diagram
- 3. Hat height modified individually.
- 4. Secondary structure pipe thickness and overall length (quantities measured for costing). 5. Slat section (quantities measures for costing).
- 6. Slat distribution according to solar orientation. In some cases this slats are distributed in an algorithmic sequence (quantities measures for
- 7. Fixed solar panel orientation south at an angle of 22 degrees. In some cases this causes shear in the "Hat" profile that can be accommodated up to
- the bending tolerance of the shading slats. 8. Primary structure - pipe thickness which varies according to span (quantities measures for





3







\$136,830










\$116,630 \$125,770



















Approach Sequence - Polyshade Builds Upon the Exiting Sustainable Practice of the Community Garden



Throughout the project students (particularly those involved in the development of the digital model) developed a





Engage in sustainable practice (solar) through consultation with PV/Solar specialists ESD providing technical learning. This based on a wider necessity to provide solutions to arid-zone shade and mitigation of heat stress in extreme temperatures. The provision of actively cooled zones promotes the use and engagement of outdoor public space.

In this instance students developed a method of communicating fabrication drawings for steelwork


fabricator (S. Diamond Steel). They learnt to interpret the digital model in terms of the appropriate

information for the fabricators i.e. 3D positioning of intersections, four-way pipe intersections and "birds mouth" profile. This involved a close working relationship with S-Diamond and learning the

importance of hardcopy and electronic fabrication information. This was particularly associated with

connection details and the structural diagram. Several students we actively involved in shop visits


4'-0"x 1'-6" conc, footing w/ #5 reber 12" α.c. 3000 psi 3"Ø steel pipe secondary "hat" structus Sustainable practice (solar) - PV Arrangement. Construction Drawings - "Hat" Section















Prototype - Cost Control and Construction







Cost -control also included full-scale fabrication of prototypical section of the project.

In this instance students were responsible for coordinating the construction of one of

the eight bays of the overall structure. This bay needed to be fully costed taking into

account primary structure, cladding, PV and fan arrangement. It also encompassed

finishes, an estimation of labor, delivery and assembly. While students were involved in some aspects of this construction it was important that they made an assessment of



Students had additional experience in resolving and coordination the fabrication sequence that also involved electrical and solar installation by professional engineers. The gained experience resolving negotiations with university campus health and safety and acquiring permission for campus installation. This involved risk assessment for delivery and installation on two sites.